Bruhat Bangalore Mahanagara Palike

O/o Executive Engineer (PC-4), No.301, 3rd Floor, Annexe -2, N R Square, Bengaluru-560002.
Email: eeprojectscentral4@gmail.com

NO: EE/PC-4/TEND/04/2023-24 Date: 17.02.2024

ADDENDUM-1

Project Name : Special Development works including Renovation to existing buildings, Electrification, etc at Freedom Park, Bengaluru.

Ref :
1. Tender Notification NO: EE/PC-4/TEND/04/2023-24 Dt: 15-02-2024.
2. Tender Number: BBMP/2023-24/BD/WORK_INDENT2092

******

Adverting to the above Tender Notification, Addendum is issued to the Bill of Quantities (Commercial Bid) in KPPP publication.

Sl No	Section of Tender & Description of Item		Mentioned in KPP portal as		To be read as	
	Item Code No.	Description of Item	Quantity	Rate (Rs) Including GST & all taxes	Quantity	Rate (Rs) Including GST & all taxes
1	99	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: old admin block Float glass panes of nominal thickness 5 mm (weight not less than 12.5kg/m²) Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	10.00	1107.00	7.70	1,436.88
2	100	Float glass panes of nominal thickness 5 mm (weight not less than 12.5kg/m²) Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	10.00	1468.00	7.70	1,905.46
3	101	Float glass panes of nominal thickness 5 mm (weight not less than 12.5kg/m² Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	10.00	1207.00	7.70	1,566.68
4	102	2nd class teak wood fillets Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	25.00	52.00	19.26	67.49
5	103	Renewal of old putty of glass panes (length) Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	30.00	39.00	23.11	50.62
6	104	Replacing granite stone slabs 100mm to 150mm thick in roofing, laid in cement mortar 1:4 (1 cement : 4 coarse sand), including necessary repairs and cement pointing with same mortar complete, including disposal of rubbish to dumping ground, scaffolding and transportation all complete as per direction of Engineer-in-Charge	10.00	1172.00	7.70	1,521.25
7	106	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	100.00	50.00	77.04	64.90
8	107	Renewing Wrought Iron or M.S. Wheel or roller of steel door or gate and fitting and fixing the same with necessary clamps, nuts and bolts/welding and erection etc. complete. Wheel above 50 mm dia. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	10.00	244.00	7.70	316.71

Sl No	Section of Tender & Description of Item		Mentioned in KPP portal as		To be read as	
	Item Code No.	Description of Item	Quantity	Rate (Rs) Including GST & all taxes	Quantity	Rate (Rs) Including GST & all taxes
9	108	Superior class teak wood including nickel plated bright finished M.S. piano hinges with necessary screws. (Old exhibition work) Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	30.00	4280.00	23.11	5,555.44
10	109	Ist class teak wood including nickel plated bright finished M.S. piano hinges with necessary screws. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	10.00	3631.00	7.70	4,713.03
11	110	Providing and fixing bright finished brass single acting spring hinges with necessary brass screws etc. complete : (For old exhibition space)-150 mm. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	30.00	658.00	23.11	854.08
12	111	Providing and fixing bright finished brass flush bolts with necessary brass screws etc. complete : (For old exhibition space)-250 mm. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	20.00	245.00	15.41	318.01
13	112	Providing and fixing bright finished brass hard drawn hooks and eyes : (For old exhibition space) 300mm. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	10.00	84.00	7.70	109.03
14	113	Providing and fixing bright finished brass hard drawn hooks and eyes : (For old exhibition space) 250mm. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	10.00	81.00	7.70	105.13
15	114	Providing and fixing bright finished brass hard drawn hooks a18nd eyes : (For old exhibition space) 200mm. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In	10.00	72.00	7.70	93.45
16	115	Providing and fixing bright finished brass hard drawn hooks and eyes : (For old exhibition space) 150. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	10.00	58.00	7.70	75.28
17	116	Providing and fixing bright finished casement window fasteners or peg stays to windows/ ventilators with necessary welding and machine screws etc. complete. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	2.00	500.00	1.54	649.00
18	117	Cleaning of terrace/loft water storage tank (inside surface area) upto 2000 litre capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba all complete as per direction of Engineer-in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre) (if during cleaning any GI fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account)-Info cooridor marker wall. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	5000.00	32.00	3868.47	41.36

Sl No	Section of Tender & Description of Item		Mentioned in KPP portal as		To be read as	
	Item Code No.	Description of Item	Quantity	Rate (Rs) Including GST & all taxes	Quantity	Rate (Rs) Including GST & all taxes
19	118	Cleaning and desilting of gully trap chamber, including removal of rubbish mixed with earth etc. and disposal of same, all as per the direction of Engineer-in- charge. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	50.00	78.00	38.52	101.24
20	119	Cleaning of chocked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction m^3 jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm dia upto 300mm dia. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	2500.00	291.00	1926.03	377.72
21	120	Cleaning of under ground sump, Over Head R.C.C. Tank (independent staging) including disposal of slit and rubbish, all as per direction of Engineer-In-Charge. The cleaning shall consist following operations: Tank shall be emptied of water by pumping & bottom shall be cleaned of silt and other deposits. (ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	400.00	67.00	308.15	86.97
22	121	Disconnecting damaged overhead/terrace PVC water storage tank of any size from water supply line and removing from the terrace including shifting at ground level as per direction of Engineer-in-charge. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	2.00	295.00	1.54	382.91
23	122	Cutting holes of required size in brick masonry wall for fixing of exhaust fan including providing and fixing 300 mm dia PVC pipe conforming BIS-12818 and making good the same with CM 1:4 etc. complete as per direction of Engineer-in-charge. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	10.00	221.00	7.70	286.86
24	123	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	100.00	3.00	77.12	3.89
5	128	Removing the old paint or polish from wood and / or wood based surface with paint remover of approved brand / manufacturer and making surface even including cost of materials, labour, complete as per specifications. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	20.00	95.00	15.41	123.31

Sl No	Section of Tender & Description of Item		Mentioned in the portal as		To be read as	
	Item Code No.	Description of Item	Quantity	Rate (Rs) Including GST & all taxes	Quantity	Rate (Rs) Including GST & all taxes
26	129	Removing the old paint or polish from wood and / or wood based surface with caustic soda solution and making surface even including cost of materials, labour, complete as per specifications. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	25.00	72.00	19.26	93.45
27	130	Removing the old paint from steel and / or other metal surface with paint remover of approved brand / manufacturer cleaning and making surface even including cost of material, labour, complete as per specifications. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	25.00	93.00	19.26	120.71
28	132	Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit shutter thickness complete. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	15.00	236.00	11.56	306.32
29	133	Treatment at points of contact of wood work by chemical emulsion Chlorpyriphos/ Lindane (in oil or kerosene based solution) @ 0.5 litres per hole by drilling 6 mm dia holes at downward angle of 45 degree at 150 mm centre to centre and sealing the same. Complete with all lead and lift including transportation, loading & Unloading, complete as per the directions of Engineer In Charge	45.00	350.00	34.67	454.30

Other terms & conditions remain unchanged.

17.2.2024

Executive Engineer
Project Central -4
Bruhat Bengaluru Mahanagara Palike

Copy submitted to:

1. Chief Engineer (Projects Central) for kind information.
2. Superintending Engineer (Projects Central) for kind information.
3. Office Copy.